



No.: IISER–K/Civil/22-23/Q09

Date: 13.06.2022

NOTICE INVITING QUOTATION

Indian Institute of Science Education and Research – Kolkata, Mohanpur Campus, Mohanpur - 741246, invites sealed item rate quotations for the under mentioned work from eligible and experienced civil contractors of CPWD/PWD/MES/KMDA/Railway/others Government Department and or other bonafide agencies dealing with Civil building works.

Name of Work: Renovation work for counter type granite shelf in the common room of DMS department at third floor of C. V. Raman AAC Building of IISER Kolkata.

- | | |
|---|-----------------|
| (a) Estimated Cost | : Rs. 59,730.00 |
| (b) Earnest Money | : N.A. |
| (c) Application for Quotation | : N.A. |
| (d) Receipt and open of Quotation Paper | |
| Up to 15.00 and 15.30 hrs of | : 23.06.2022 |
| (e) Time Allowed for works | : 30 days. |

Quotation documents may be downloaded from the Institute website (<http://www.iiserkol.ac.in/announcements/tenders>) w. e. f. 14/06/2022 to 23/06/2022(up to 15.00 hrs).

Quotation paper in complete shape should be submitted along with your comparative and justified rate as per the schedule of items including all relevant documents like copies of Trade license, PAN etc, GST Registration, IT Return for the last three financial years in a sealed cover, addressed to the undersigned super scribing name of work so as to reach him within 15.00 hrs of **23.06.2022** positively for further details contact under mentioned for clarification etc.

Please note that the Competent Authority reserve the right to accept or reject any or all quotations without assigning any reason whatsoever.

**Superintendent Engineer
IISER – Kolkata.**

Copy to:

1. AR(F & A), IISER-K.
2. Notice Board, IISER-K & File.

Bill of quantities

Name of work :- Renovation work for counter type granite shelf in the common room of DMS department at third floor of C. V. Raman AAC Building of IISER Kolkata.

Item No.	Sub-heads and items of work	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
1	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	sqm	1		
2	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. (i) For thickness of tiles 10 mm to 25 mm sources : 4 graded stone aggregate 20 mm nominal size	sqm	3		
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : (i) 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural derived from natural sources)	cum	0.4		
4	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels.				
	(a) Granite stone slab colour black, Cherry/Ruby red (i) Area of slab over 0.50 sqm	sqm	4		
5	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge.				
	(i) Granite work	metre	18		
6	Extra for fixing marble /granite stone, over and above corresponding basic item, in facia and drops of width upto 150 mm with epoxy resin based adhesive, including cleaning etc. complete.	metre	20		

Item No.	Sub-heads and items of work	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
7	Extra for providing opening of required size & shape for wash basin/ kitchen sink in kitchen platform, vanity counter and similar location in marble/Granite/stone work, including necessary holes for pillar taps etc. including moulding, rubbing and polishing of cut edges etc. complete.	each	2		
8	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete.				
	(i) Size of Tile 600x600 mm	sqm	4		
9	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required :				
	(a) Kitchen sink without drain board : (i) 610x460 mm bowl depth 200 mm	each	1		
10	Supplying, fitting and fixing Black Stone slab used in Kitchen slab, alcove, wardrobe etc. laid and jointed with necessary adhesive Cement mortar (1:2) including grinding or polishing as per direction of Engineer-in -Charge in Ground Floor.				
	(a) Slab Thickness 20 to 25 mm	sqm	5		
	(b) Slab Thickness above 25 mm and upto 37.5 mm	sqm	6		

Total Rs.=